



- NOTES:
1. WARRANTY PLANTS AND TREES FOR TWO YEARS AFTER FINAL ACCEPTANCE. REPLACE DEAD OR DYING MATERIALS NOT IN VIGOROUS, THRIVING CONDITION AS SOON AS WEATHER PERMITS.
 2. DETERMINE LOCATIONS OF UNDERGROUND UTILITIES AND PERFORM WORK IN A MANNER WHICH WILL AVOID POSSIBLE DAMAGE.
 3. PLANTS SHALL BE SPECIMEN QUALITY, TYPICAL OF THEIR SPECIES OR VARIETY.
 4. PLANT TREES AND SHRUBS IN PITS 12" LARGER THAN TREE BALL, BACKFILL WITH A MIX OF 2 PARTS TOPSOIL, 1 PART COMPOST OR PEAT, AND 1 PART SAND.
 5. INSTALL GEOTEXTILE WEED RESTRICTOR FABRIC BETWEEN SOIL AND CRUSHED ROCK.
 6. ALL TREES IN SEED OR TURF AREAS SHALL RECEIVE MULCH RINGS.
 7. EXISTING TURF AREAS THAT ARE DISTURBED DURING CONSTRUCTION, ESTABLISHMENT AND THE MAINTENANCE PERIOD SHALL BE RESTORED WITH NEW SOD TO MATCH EXISTING TURF SPECIES. DISTURBED NATIVE AREAS WHICH ARE TO REMAIN SHALL BE OVER SEEDDED AND RESTORED WITH SPECIFIED SEED MIX.
 8. CONTRACTOR SHALL OVER SEED ALL MAINTENANCE OR SERVICE ACCESS BENCHES AND ROADS WITH SPECIFIED SEED MIX UNLESS OTHERWISE NOTED ON THE PLANS.

Plant Material Schedule

| | | | |
|---|--------------------------------|---|-------------|
| Coniferous Trees | | | |
| CS | 12" Colorado Spruce | Picea pungens | 3 12' ht. |
| Deciduous Trees | | | |
| SG | Sienna Glen Maple | Acer x Freemanii 'Sienna' | 6 2.5' cal. |
| SO | Swamp White Oak | Quercus bicolor | 2 2.5' cal. |
| NM | Norway Maple 'Emerald Queen' | Acer Platanoides 'Emerald Queen' | 2 2.5' cal. |
| KC | Kentucky Coffeetree | Gymnocladus dioica | 2 2.5' cal. |
| IH | Imperial Honeylocust | Gleditsia triacanthos Inermis Imperial | 7 2.5' cal. |
| L | Glenleven Little Leaf Linden | Tilia Cordata 'Glenleven' | 2 2.5' cal. |
| CC | Canada Red Chokecherry | Prunus Virginia 'Canada Red' | 2 2' cal. |
| RB | Western River Birch | Betula occidentalis | 4 6' ht. |
| FC | Fremont Cottonwood | Populus fremontii | 5 2.5' cal. |
| LC | Lanceleaf Cottonwood | Populus Angustifolia | 3 2.5' cal. |
| Shrubs, Perennials & Grasses | | | |
| All shrubs #5 container | | | |
| R | Rosa 'Nearly Wild' | Rosa woodsii x 'Nearly Wild' | 14 #5 cont. |
| D | Red-Osier Dogwood | Cornus sericea 'Coloradensis' | 20 #5 cont. |
| B | Compact Burning Bush | Euonymus alatus 'Compactus' | 19 #5 cont. |
| S | Autumn Brilliance Serviceberry | Amelanchier Grandiflora 'Autumn Brilliance' | 19 #5 cont. |
| C | Green Mound Currant | Ribes Alpinum 'Green Mound' | 21 #5 cont. |
| Riparian Shrub Plugs | | | |
| 200 plugs, 10 cu. Inch each | | | |
| | Rocky Mountain Maple | Acer glabrum | |
| | Thinleaf Alder | Alnus incana ssp. Tenuifolia | |
| | Bebb Willow | Salix bebbiana | |
| | Geyer's Willow | Salix geyeriana | |
| | Coyote (Sandbar) Willow | Salix exigua | |
| | Chokecherry | Prunus virginiana | |
| Native Seed Mix | | | |
| Rate: .82 lb per 1,000 sq. ft. | | | |
| | 20% Mountain Brome | | |
| | 20% Slender Wheatgrass | | |
| | 20% Western Wheatgrass | | |
| | 15% Thickspike Wheatgrass | | |
| | 10% Idaho Fescue | | |
| | 5% Indian Ricegrass | | |
| | 5% Sideoats Grama | | |
| | 5% Bluebunch Wheatgrass | | |

| Computer File Information | | Sheet Revisions | | | |  |  118 West Sixth St. Suite 200 Glenwood Springs, CO 81601 970.945.1004 www.sgm-inc.com | For Review Only | | Two Rivers Park Improvements Project Civil Plans | | | Project No./Code | |
|--|--|----------------------|------|----------|-------|---|---|-----------------|--|--|--|---------------|------------------|--|
| Print Date: 7-10-19 | | Rev. | Date | Comments | Init. | | | No Revisions: - | | Engineer: --- Structure --- Numbers --- Sheet Subset: 1 of -- | | | No.: -- | |
| Last Modification Date: | | <input type="text"/> | | | | | | Revised: - | | | | | Code: -- | |
| Drawing File Name: TwoRivers-TitleBlock | | <input type="text"/> | | | | | | Void: - | | Drawn By: --- | | Sheet | | |
| Autocad Ver. 2018 Scale: As Shown Units: | | <input type="text"/> | | | | | | | | Subset Sheets: 1 of -- | | Number: C33.1 | | |
| SGM Project No.: 2018-476.001 | | <input type="text"/> | | | | | | | | | | | | |